



Security System Integration

Scope of Infrastructure Services **Dixon Electric**

The proposal includes supplying all labor, material and equipment to perform work as spelled out in UK's request for proposal and the following outline of work supplied by Dixon Electric.

. We have included installation of door power supplies and controls.

This quotation includes all labor, material and equipment to install Pole Cameras as follows to include twenty three (23) locations. We have included all concrete and related work to pour pole bases, all required digging and boring to get raceways back to corresponding building and poles with anchor bolts. Our price includes all cabling back to communication room and connections at equipment end. We have included required labor and material to install communication room equipment supplied by someone else..

This quotation includes all labor, material and equipment to install Exterior Notification Stations as follows to include twenty six (26) locations. We have included all concrete and related work to pour bases, all required digging and boring to get raceways back to corresponding building. Price is to install Notification Stations and. Our price includes all cabling back to communication room and connections at equipment end. We have included required labor and material to install communication room equipment.

This quotation includes all labor, material and equipment to install Building Mounted Cameras as follows to include nineteen (19) building mounted cameras and one (1) ped-way mounted camera. We have included mounting of cameras and all related raceways and cabling to closest Communication Closet. We have included required labor and material to install communication room equipment .This quotation includes all labor, material and equipment to install Interior Notification Speakers as spelled out on UK's offertory's scope of work dated 11-26-2012 included in addendum 4. The amount of speakers included in our proposal is listed per building on the offertory's scope of work mentioned above. Our price includes running EMT conduit to each speaker location and installing a Cat-5 cable. We have included mounting of speakers and all related raceways and cabling to closest Communication Closet. We have included required labor and material to install communication room equipment.

This quotation includes all labor, material and equipment to perform Interior Work as follows to include forty one (41) buildings. Our price includes running EMT conduit to each door location and installing required cable. We have included mounting and wiring of card readers and cameras and all related raceways and cabling to closest Communication Closet. We have included required labor and material to install communication room equipment.



Security System Integration

This quotation covers all labor, material and equipment to perform work for the Legacy Building as follows to include six (6) buildings. In the Bio Pharmacy-COP building we have only included installing new hardware supplied by someone else in the Communication Room. At the VDL building interior work we have only included installing new communication room equipment and (12) access control. We have not included any new cables for the (12) access control devices. In the following buildings: Smith Hall, Ingels Hall, Baldwin Hall and Roselle Hall we have included labor and material to install new cameras and access control devices as shown on the drawings supplied in addendum 4.

Procedures to meet UK required completion dates:

The following dates are based on receiving a purchase order by January 14, 2013. Our goal is to meet the following dates as spelled out by UK in their request for proposal and addendums through 5.

- Card Access base system test by 3-1-13.
- Fully operational Card Access system by 4-1-13.
- Legacy Interior Building items highlighted in yellow as spelled out in section 7.8, page 76 dated 11-26-12 by 8-1-13.
- Legacy Interior Building items highlighted in blue as spelled out in section 7.8, page 76 dated 11-26-12 by 12-31-13.
- All other work not spelled out above will be complete by 12-31-13.

Murl Caudill will project manage this project through its completion. Under Murl there will be five (5) field foremen with crews working on interior work and three (3) foremen with crews working on exterior projects. These will be our minimum crews through completion of phase 1. We may have to adjust our crews to accommodate required completion dates due to weather and other un-foreseen issues. We have included night and weekend work required to accommodate Campus life and keep project on schedule. We will have weekly progress meetings to keep vendor updated with progress and expected completion dates. This will assist them in scheduling their Tec on Campus.